

## MMSD Planned Construction or Services Bids\*

April 1, 2025 - March 31, 2026

Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
TBD	<b>Primary Clarifier 1, 2, 4, 8, and 9 Repairs at SSWRF</b> - The scope consists of purchasing flights, chains, sprockets, and bearing sleeves for these 5 primary clarifiers. The scope also includes removing the existing flights, chains, sprockets, and bearing sleeves from primary clarifiers and installing the corresponding new equipment.	2	2025
S06038C35	<b>SSWRF Thickened Primary Sludge Lines 1 and 2 Replacement</b> - Replace 2 TPS lines within the Digester Gallery in lieu of their current buried alignment	2	2025
S06045C20	<b>Carbon Media Replacement at SSWRF</b> - The scope consists of removing and disposing of the carbon media in three odor control tanks at the Thickening Building and then installing new carbon media supplied by MMSD. The scope also consists of removing and disposing of the carbon media in one of the siloxane tanks in the Digester Gallery and installing new carbon media approximately every four months over the course of three years for a total of 12 replacements. The Contractor shall initially use media provided by MMSD for the siloxane tanks but shall purchase media after the existing MMSD provided media is consumed.	2	2025
TBD	<b>Milwaukee County Grounds Wall Repairs and Levee Floodwall Repairs</b> - This work will consist of concrete wall and floodwall repairs to wall surfaces and construction joints. The work will also include masonry restoration, cleaning, and repointing of mortar joints.	2	2025
W40009C01	<b>KK River Jackson Park: Demolition, Salvage &amp; Recycling at 3460 W. Leeds Place</b> - The scope includes demolition, salvage and recycling of a building, earthwork, landfill disposal of soil, and surface restoration at 3460 West Leeds Place in Milwaukee.	2	2025

## MMSD Planned Construction or Services Bids\*

April 1, 2025 - March 31, 2026

Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
J06089C02	<b>Flow Meter Replacement at Jones Island WRF</b> - The scope includes replacing five large influent and secondary effluent flow meters (High level, Low Level, & ISS Pump Out in bldg. 204, Disinfection #1 and #2 in bldg. 245)	2	2025
J01019C01	<b>Jones Island Force Main Improvements</b> - The scope includes cleaning, televising, spot repairs at five locations, and interior steel surface recoating for the rehabilitation of a 72-inch diameter force main at the Jones Island Water Reclamation Facility.	2	2025
1739	<b>Spare Augers for Screw Conveyors in D&amp;D</b> - The District will advertise a project to procure spare augers for the following screw conveyors: Main Recycle Screw Conveyor, Dryer Feed Screw Conveyor, Recycle Bin Offload Screw Conveyor.	2	2025
G98026C01	<b>2024 Fresh Coast Highways</b> - The scope includes adding GI features that may include bioswales, native landscaping, and stormwater trees to the project area around the Port Overpass to capture stormwater from the highways and neighboring roads.	2	2025
C03014C01	<b>Greenfield Park and Underwood Creek Pump Stations Upgrades</b> - The scope includes pump rehabilitations, replacement of mechanical, electrical, and control systems, and new backup generators.	2	2025

## MMSD Planned Construction or Services Bids\*

April 1, 2025 - March 31, 2026

Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
C02012C01	<b>10th Avenue MIS Lateral Reconstruction</b> - Open cut excavation for the replacement of 5 sewer laterals and one local sewer segment.	3	2025
S01013C02	<b>Clean Water Research Center</b> - Construction of a new clean water research center at the South Shore Water Reclamation Facility. Contract scope included foundation excavation, earth retention, structural concrete, masonry building, roofing, building HVAC mechanical, building electrical services, instrumentation and controls, facility solar panels, and installation of owner-procured process mechanical equipment.	3	2025
C03013C01	<b>Oklahoma Avenue MIS Capacity Improvements</b> - Construction of 3,300 LF of new 48" diameter sewer via microtunneling. Contract also includes relocation of local utilities, abandonment of a pump station and associated site restoration.	3	2025
M01044C01	<b>HQ and Lab Buildings Remodel</b> - The scope includes the full remodel of MMSD HQ Building Floors 1 - 4.	3	2025
W20033C01	<b>Menomonee River Levee System Improvements</b> - The scope includes levee and floodwall freeboard improvements along with storm sewer closure improvements integral with or near the Hart Park levee system. Includes approximately: 1,800 feet of earthen levee raise, 750 feet of reinforced concrete floodwall raise, 100 feet of 30-inch storm sewer with flap gate, 72-inch storm sewer new structure with internal flap gate, 90 feet of 8-inch sanitary sewer, 1,800 feet of paved maintenance drive, and site restoration.	4	2025

## MMSD Planned Construction or Services Bids\*

April 1, 2025 - March 31, 2026

Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
J04057C01	<b>Milorganite® Dryer Exhaust Duct Header and Damper Replacement</b> - Construction for the removal and replacement of approximately 750 linear feet of existing 36" to 96" diameter stainless dryer exhaust ducting, installation of owner procured guillotine dampers, installation of owner procured butterfly dampers, and associated electrical instrumentation and controls work.	4	2025
S01015C01	<b>Grit Equipment Replacement</b> - The scope includes replacement or rehabilitation of the following equipment in the Preliminary Treatment Facility: Grit slurry cups, dewatering escalators (snails), grit/screenings conveyors, primary sludge screenings conveyor, and winches for the grit load out containers.	4	2025
C05041C04	<b>Basin H MIS Remediation and Sewer Rehabilitation</b> - Rehabilitation of the MIS by installing joint seals and remediating longitudinal cracks in pipe segments, and rehabilitating manholes located in Basin "H" of the Central MIS sewer system.	1	2026
J06083C01	<b>HVAC System Improvements</b> - Replace and updated heating, ventilation and air conditioning (HVAC) equipment and controls in Buildings 234 (RAS Pump Station), 235 (WAS Pump Station), 243 (Chemical Unloading Facility), 256 (Thickening Facility), 257 (Equalization and Blend Facility), 258 (Dewatering and Drying Facility), 263C (Inline Pump Station), 279 (Operations Building) and 289A (Powerhouse - boiler room addition).	1	2026
G98032C01	<b>Holt Avenue Overpass - Green Highways</b> - The project will consist of the construction of bioretention basins, native vegetation and landscaping, site grading, surface restoration, underground storm sewer piping and structures, installation of rock-lined channels, and a five-year vegetation maintenance contract for the native vegetation. As design progresses, more details can be released.	1	2026

## MMSD Planned Construction or Services Bids\*

April 1, 2025 - March 31, 2026

Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
J03006C01 and S03005C01	<b>Disinfection Process Improvements</b> - Construction of a new disinfection processes at Jones Island WRF and South Shore WRF including new UV disinfection system for flows up to 135-150 MGD, and chemical disinfection system for higher flows. Improvements include new equipment, pumps, piping, valves, chemical storage tanks, buildings, heating, ventilation, and air conditioning (HVAC), electrical, controls, walkways, and site work.	1	2026
MCRR 1711	<b>Dryer and Classification Baghouse Explosion Suppression System Repairs</b> - This project consists of the removal of existing discharge suppressors and associated components and replacing in kind. The project location is located on the 6th floor of the Dewatering and Drying (D&D facility). The components are located on dust ducts and on the baghouses themselves.	1	2026
<b><i>*All schedules are estimates and subject to change. This list will be updated quarterly.</i></b>			