

MMSD Planned Construction or Services Bids*

July 1, 2024 - June 30, 2025

Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
S06045C21	Turf Grass Restoration at South Shore WRF - The scope includes removing clay fill, installing topsoil, and planting turfgrass at 21 locations at the South Shore WRF.	3	2024
J04077C01	Odor Control at Equalization and Blend (E&B) Facility - The scope consists of adding a new treatment stage for E&B tank air emissions. The improvements include a new biological scrubber located upstream of a new carbon adsorption unit, odorous air ductwork and piping, and all associated equipment. The E&B building will be modified to add a vertical extension to the odor control room above the existing roof line, including new walls, removable roof, and door access. Associated improvements include HVAC modifications and new controls, drain pump and piping, lighting, electrical, and instrumentation and controls work.	3	2024
M01048C01	Security Improvements - The scope replaces the access control, security camera, and visitor management systems at the Jones Island Water Reclamation Facility (WRF), South Shore WRF, Headquarters, Laboratory, and 13th Street facility. The contract will provide a new seamless system for access control and visitor management. The contract will replace all existing access control, visitor management and video surveillance systems, expand surveillance capabilities, and integrate surveillance into the access control systems	3	2024
S06045C20	Siloxane Treatment Media Replacements at South Shore Water Reclamation Facility - The scope includes removing the existing carbon media from the siloxane treatment tanks at the SSWRF and replacing it with new media as needed. This will be a 2 year contract with an anticipated 16 total media changeouts.	3	2024
J06080C27	Asphalt Replacement at Jones Island WRF - Remove and replace approximately 31,000 square feet of 6" asphalt at Jones Island WRF.	3	2024
TBD	Spare Grit Pump 1 Repairs at South Shore WRF - Replace the impeller, bearings, shaft, seal, etc. for Spare Grit Pump 1 at South Shore WRF	3	2024
J02012C01	Aeration System Improvements - The scope includes repairing leaking mechanical joints on existing 48-inch, 54-inch, and 6--inch diameter cast iron pipe using internal seals and external clamps.	3	2024
C03014C01	Greenfield Park and Underwood Creek Pump Stations Upgrades - The scope includes rehabilitation or replacement of process mechanical, electrical and control systems at two conveyance pump stations.	3	2024
W40009C01	KK River Jackson Park: Demolition, Salvage & Recycling at 3460 W. Leeds Place - The scope includes demolition, salvage and recycling of a building, earthwork, landfill disposal of soil, and surface restoration at 3460 West Leeds Place in Milwaukee, WI.	3	2024

MMSD Planned Construction or Services Bids*

July 1, 2024 - June 30, 2025

Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
C98059C11	Collection System Point Repairs - Address CIPP liner tears, utility bore throughs and connection system integrity at 4 locations.	3	2024
J06080C22	Jones Island East Plant Mixed Liquor Channel Repairs - Replace the diffusers and containers on the west end of the Southern East Plant Mixed Liquor Channel which were damaged by the W3 pipe.	3	2024
TBD	On-Call Primary Clarifier Repairs at South Shore WRF - Make repairs to the Primary Clarifiers at South Shore WRF as needed over the next 5 years.	3	2024
W40009C02	KK River Jackson Park: Sport Courts and Soccer Fields - The scope consists of construction of sport courts and soccer fields in Jackson Park located at 3500 W. Forest Home Avenue, Milwaukee, Wisconsin. The work includes earthwork, tree removal, landfill disposal of soil, pavement placement and surfacing, installation of court furnishings, storm sewer modifications, construction of a bioswale and surface restoration.	3	2024
S06038C34	Digester 12 Heat Exchangers and Hot Water Pumps Replacement - Replace 2 Heat Exchangers, 2 Hot Water Pumps and associated manual valves for this Digester.	3	2024
TBD	Sediment Removal - Honey Creek Concrete Lined Channel - The contractor shall remove and dispose of sediment from a concrete lined portion of the Honey Creek in accordance with local and state requirements.	4	2024
TBD	Boulder Installation - Various MMSD Properties - The Contractor shall furnish and install approximately 100 boulders between 36 - 42 inches in diameter and no more than five feet apart across three sites.	4	2024
S02017C01	Process Air Header Improvements - The scope includes replacing four buried 30-inch blower branch pipes from the Blower and Generator Building 326 to the buried 60/90-inch main air header, patch areas of corrosion on the buried 60/90-inch main air header adjacent to the blower branch pipes, and replacing 30-inch blower branch pipe isolation valves and expansion joints inside Building 326. The new buried piping will be carbon steel with external coating. The scope also includes removal of an existing coal tar enamel coating that contains asbestos on portions of the branch pipes, maintaining the existing cathodic protection system through and after construction, and surface restoration.	4	2024
S06038C35	SSWRF Thickened Primary Sludge Lines 1 and 2 Replacement - Replace 2 TPS lines within the Digester Gallery in lieu of their current buried alignment	4	2024

MMSD Planned Construction or Services Bids*

July 1, 2024 - June 30, 2025

Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
TBD	SSWRF Primary Sludge Screens Replacement - The scope includes replacement of the 3 existing primary sludge screens with 3 new primary sludge screens	4	2024
J04076C01	Compressed Air System Upgrades - The scope includes replacing nine existing compressors in three buildings with two new centralized compressor systems in two buildings; replacing two compressors and removing seven compressors. The scope also includes new air dryers, storage tanks, mechanical piping, electrical, instrumentation and controls.	4	2024
S02018C01	RAS Pumps Replacement - The scope includes replacing eight return activated sludge (RAS) pumps and motors. Mechanical work includes replacement of pump suction and discharge piping, expansion joints, check valves, isolation valves and piping supports. Electrical work includes replacement of the pump motors, variable frequency drives, 480V switchboard breakers, and associated conduit and wiring. Control work includes replacement of RAS pump instrumentation and transmitters. Other work includes removal of concrete, providing new concrete equipment pads, masonry, doors, finishes and painting.	4	2024
W10004C01	Milwaukee River Habitat Enhancement - Estabrook Falls - Remove bedrock from the bed of the Milwaukee River to improve hydraulic conditions for passage of native fish. Restore vegetation.	4	2024
S06050C01	HVAC Systems Improvements in Buildings 378 & 380 - The scope includes replacing HVAC equipment at the Administration Building (378) and Maintenance Building (380). The scope also includes replacing the acoustical drop ceiling and lens covers for existing light fixtures.	4	2024
C98065C01	Separate Sewer Outfall Abandonment - The scope consists of decommissioning and abandonment of eight Sanitary Sewer Overflow Outfall sites. Decommissioning and abandonment includes: removing all equipment, including gates, stoplogs, monitoring equipment, telemetry, and I&C. The scope also includes removing electrical service as necessary to decommission the site and properly bulkheading and abandoning the outfall pipe per state standards/requirements.	4	2024
M01044C01	HQ and Lab Buildings Remodel - The scope includes remodel of the 1st and 4th floor at MMSD HQ. HVAC improvements and ADA compliant restrooms are also included.	1	2025
J06086C01	Building Roof Replacement Phase 4 at Jones Island WRF - The scope includes the replacement of the roofs on three buildings at the Jones Island Water Reclamation Facility.	1	2025
S06048C01	Building Roof Replacement Phase 5 at the South Shore WRF - The scope includes the replacement of the roofs on five buildings at the South Shore Water Reclamation Facility.	1	2025

MMSD Planned Construction or Services Bids*

July 1, 2024 - June 30, 2025

Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
G98026C01	2024 Fresh Coast Highways - The scope includes adding GI features that may include bioswales, native landscaping, and stormwater trees to the project area around the Port Overpass to capture stormwater from the highways and neighboring roads.	1	2025
W20033C01	Menomonee River Levee System Accreditation - The scope includes levee and floodwall freeboard improvements along with storm sewer closure improvements integral with or near the Hart Park levee system.	2	2025
J01019C01	Jones Island Force Main Improvements - The scope includes cleaning, televising, spot repairs at five locations, and interior steel surface recoating for the rehabilitation of a 72-inch diameter force main at the Jones Island Water Reclamation Facility.	2	2025
C98063E04	MIS Siphons Preliminary Engineering - Phase 2 - The scope includes condition assessment of siphons to be identified for Phase 2. Siphons will be isolated, cleaned, and then assessed with CCTV and other multi-sensor inspection equipment as specified.	2	2025

**All schedules are estimates and subject to change. This list will be updated quarterly.*