

MMSD Planned Construction or Services Bids*

January 1, 2025 - December 31, 2025

Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
P01005C13	Interplant Sludge System Routine Cleaning - Routine cleaning (pigging) of the four interplant sludge pipelines.	1	2025
C98068C01	Rehabilitation of Individual Pipe Segments - The scope consists of the rehabilitation of four Metropolitan Interceptor Sewer pipe segments through CIPP lining, geopolymer lining or spiral-wound pipe lining.	1	2025
G98004P19	8359 S. 5th Ave. Drainage Ditch - Clearing & grubbing, grading, and surface restoration to increase capacity of drainage ditch on District-owned property.	1	2025
C98055C08	Generator Replacements at 13th St. Facility and Range Line Road Pump Station - Replace emergency backup generators at 13th St. and BS0506.	1	2025
W10004C01	Milwaukee River Habitat Enhancement - Estabrook Falls - The scope includes removal of bedrock from the bed of the Milwaukee River to improve hydraulic conditions for passage of native fish and restoration of vegetation in access and staging areas.	1	2025

MMSD Planned Construction or Services Bids*

January 1, 2025 - December 31, 2025

Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
C98065C01	Separate Sewer Outfall Abandonment - The scope consists of decommissioning and abandonment of eight Sanitary Sewer Overflow Outfall sites. Decommissioning and abandonment includes: removing all equipment, including gates, stoplogs, monitoring equipment, telemetry, and I&C. The scope also includes removing electrical service as necessary to decommission the site and properly bulkheading and abandoning the outfall pipe per state standards/requirements.	1	2025
J04077C01	Equalization and Blend Tanks Odor Control Upgrade - The scope will add a new treatment stage for Equalization and Blend (E&B) tank air emissions. The improvements include a new biological treatment unit located upstream of a new carbon adsorption unit, and associated odorous air piping. The E&B building will be modified to add a vertical extension to the odor control room above the existing roof line, including new walls, removable roof, and door access. Associated improvements include HVAC, drain piping, lighting, electrical, instrumentation and controls work.	1	2025
S06045C20	Carbon Media Replacement at SSWRF - The scope consists of removing and disposing of the carbon media in three odor control tanks at the Thickening Building and then installing new carbon media supplied by MMSD. The scope also consists of removing and disposing of the carbon media in one of the siloxane tanks in the Digester Gallery and installing new carbon media approximately every four months over the course of three years for a total of 12 replacements. The Contractor shall initially use media provided by MMSD for the siloxane tanks but shall purchase media after the existing MMSD provided media is consumed.	1	2025
J06086C01	Building Roof Replacement Phase 4 at Jones Island WRF - The scope includes the replacement of the roofs on two buildings at the Jones Island Water Reclamation Facility.	1	2025
S06048C01	Building Roof Replacement Phase 5 at the South Shore WRF - The scope includes the replacement of the roofs on five buildings at the South Shore Water Reclamation Facility.	1	2025

MMSD Planned Construction or Services Bids*

January 1, 2025 - December 31, 2025

Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
TBD	Primary Clarifier On-Call Repairs at SSWRF - The scope consists of purchasing and storing flights, chains, sprockets, and bearing sleeves for the primary clarifiers at the Contractor's facility. The scope also includes removing the existing flights, chains, sprockets, and bearing sleeves from primary clarifiers and installing the corresponding new equipment as required over a three year period as needed.	1	2025
W40009C01	KK River Jackson Park: Demolition, Salvage & Recycling at 3460 W. Leeds Place - The scope includes demolition, salvage and recycling of a building, earthwork, landfill disposal of soil, and surface restoration at 3460 West Leeds Place in Milwaukee.	2	2025
J01019C01	Jones Island Force Main Improvements - The scope includes cleaning, televising, spot repairs at five locations, and interior steel surface recoating for the rehabilitation of a 72-inch diameter force main at the Jones Island Water Reclamation Facility.	2	2025
G98026C01	2024 Fresh Coast Highways - The scope includes adding GI features that may include bioswales, native landscaping, and stormwater trees to the project area around the Port Overpass to capture stormwater from the highways and neighboring roads.	2	2025
C98044C01	MIS Abandonment in Various Locations - Abandonment and cementitious fill of inactive manholes and pipes throughout the conveyance system.	2	2025

MMSD Planned Construction or Services Bids*

January 1, 2025 - December 31, 2025

Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
C03014C01	Greenfield Park and Underwood Creek Pump Stations Upgrades - The scope includes rehabilitation or replacement of process mechanical, electrical and control systems at two conveyance pump stations.	3	2025
S01013C02	Clean Water Research Center - Construction of research facility at the SSWRF for the piloting of new wastewater treatment technologies. Contract includes excavation, foundation work, building construction, building electrical, building mechanicals, interior buildout of laboratory and office spaces, and installation of wastewater pilot equipment.	3	2025
C03013C01	Oklahoma Avenue MIS Capacity Improvements - Construction of 3,200 LF of new 48" diameter sewer via microtunneling. Contract also includes relocation of local utilities, abandonment of a pump station and associated site restoration.	3	2025
C98063E04	MIS Siphons Preliminary Engineering - The scope includes condition assessment of 39 inverted siphons and pressurized pipes throughout the conveyance system.	4	2025
M01044C01	HQ and Lab Buildings Remodel - The scope includes the remodel of Floors 1 through 4 of the MMSD HQ Building and Floor 2 of the Laboratory building.	4	2025

MMSD Planned Construction or Services Bids*

January 1, 2025 - December 31, 2025

Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
S01015C01	Grit Equipment Replacement - The scope includes replacement or rehabilitation of the following equipment in the Preliminary Treatment Facility: Grit slurry cups, dewatering escalators (snails), grit/screenings conveyors, primary sludge screenings conveyor, and winches for the grit load out containers.	4	2025
W11031C02	North 30th Street Corridor Wet Weather Relief - West - Construction of 30MG stormwater basin along with conveyance system improvements west of the railroad tracks on the former Bee Bus Lines property. Improvements include 30MG stormwater detention basin, 1,700 feet of double 7-ft by 8-ft box culverts, 1,700 feet of street reconstruction, new stormwater outfall to Lincoln Creek, 10 acres surface restoration and creation of public space (native vegetation, green infrastructure, trails).	4	2025

****All schedules are estimates and subject to change. This list will be updated quarterly.***