

MMSD Planned Construction or Services Bids*

October 1, 2024 - September 30, 2025

Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
TBD	Boulder Installation - Various MMSD Properties - The Contractor shall furnish and install approximately 100 boulders between 36 - 42 inches in diameter and no more than five feet apart across three sites.	4	2024
S06050C01	HVAC Systems Improvements in Buildings 378 & 380 - The scope includes replacing HVAC equipment at the Administration Building (378) and Maintenance Building (380). The scope also includes replacing the acoustical drop ceiling and lens covers for existing light fixtures.	4	2024
J01018C08	ISS Pump 1 Repairs at JIWRP - Blast clean and recoat the interior of ISS Pump 1, replace wear rings, inspect and replace other components as necessary, reassemble, test, and restart the pump.	4	2024
S06038C37	SSWRF Primary Sludge Screens Replacement - The scope includes replacement (Base Bid) or rehabilitation (Alternate Bid) of the 3 existing primary sludge screens.	4	2024
TBD	Sediment Removal - Honey Creek Concrete Lined Channel - The contractor shall remove and dispose of sediment from a concrete lined portion of the Honey Creek in accordance with local and state requirements.	4	2024

MMSD Planned Construction or Services Bids*

October 1, 2024 - September 30, 2025

Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
J02012C01	Jones Island Aeration System Improvements - The scope includes repairing leaking mechanical joints on existing 48-inch, 54-inch, and 6--inch diameter cast iron pipe using internal seals and external clamps.	4	2024
C03014C01	Greenfield Park and Underwood Creek Pump Stations Upgrades - The scope includes rehabilitation or replacement of process mechanical, electrical and control systems at two conveyance pump stations.	4	2024
W40009C02	KK River Jackson Park: Sport Courts and Soccer Fields - The scope consists of construction of sport courts and soccer fields in Jackson Park located at 3500 W. Forest Home Avenue, Milwaukee, Wisconsin. The work includes earthwork, pavement placement and surfacing, installation of court furnishings, park lighting modifications, storm sewer modifications, construction of a bioswale, site restoration and post-construction vegetation establishment of sport turf on soccer fields (one year) and native seed and plugs in the bioswale (five years).	4	2024
S02017C01	Process Air Header Improvements - The scope includes replacing four buried 30-inch blower branch pipes from the Blower and Generator Building 326 to the buried 60/90-inch main air header, patch areas of corrosion on the buried 60/90-inch main air header adjacent to the blower branch pipes, and replacing 30-inch blower branch pipe isolation valves and expansion joints inside Building 326. The new buried piping will be carbon steel with external coating. The scope also includes removal of an existing coal tar enamel coating that contains asbestos on portions of the branch pipes, maintaining the existing cathodic protection system through and after construction, and surface restoration.	4	2024
C98059C11	Collection System Point Repairs - Address CIP liner tears, utility bore throughs, and connection integrity at various locations.	4	2024

MMSD Planned Construction or Services Bids*

October 1, 2024 - September 30, 2025

Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
TBD (within project J06075)	Employee Gate Replacements at Jones Island WRF - Replace the west employee entrance and exit gates along with the gate operator at JIWRF.	4	2024
C98061E02	Condition Assessment of Outfall Infrastructure - Phase 1 Sites - The scope includes condition assessment of outfall infrastructure at 22 sites using multi-sensor inspection equipment. NASSCO PACP and MACP scoring included. Scope includes sewer cleaning of 3 to 5 sites.	4	2024
S06038C36	High Strength Waste Facility Improvements at South Shore WRF - The scope includes installation of an additional rotary lobe pump, valves, and piping. Contractor will also provide a new LCP for the new pump, input/output signals to the PLC, and a new power circuit from the first floor electrical room.	4	2024
S06038C35	SSWRF Thickened Primary Sludge Lines 1 and 2 Replacement - Replace 2 TPS lines within the Digester Gallery in lieu of their current buried alignment	4	2024
S06045C20	Siloxane Media Replacement at SSWRF - Replace the carbon media in the siloxane treatment system at SSWRF as needed for the two year duration of the contract. Purchase additional media as needed after the existing supply has been exhausted.	4	2024

MMSD Planned Construction or Services Bids*

October 1, 2024 - September 30, 2025

Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
S02018C01	RAS Pumps Replacement - The scope includes replacing eight return activated sludge (RAS) pumps and motors. Mechanical work includes replacement of pump suction and discharge piping, expansion joints, check valves, isolation valves and piping supports. Electrical work includes replacement of the pump motors, variable frequency drives, 480V switchboard breakers, and associated conduit and wiring. Control work includes replacement of RAS pump instrumentation and transmitters. Other work includes removal of concrete, providing new concrete equipment pads, masonry, doors, finishes and painting.	4	2024
TBD (C98062)	Backup Generator Replacement at 13th St. and BS0506 - The scope includes replacing two emergency backup generators, one supporting critical IT infrastructure at 13th St. and another supporting pumps at Range Line Road Pump Station (BS0506). Scope also includes replacing automatic transfer switches.	4	2024
C98065C01	Separate Sewer Outfall Abandonment - The scope consists of decommissioning and abandonment of eight Sanitary Sewer Overflow Outfall sites. Decommissioning and abandonment includes: removing all equipment, including gates, stoplogs, monitoring equipment, telemetry, and I&C. The scope also includes removing electrical service as necessary to decommission the site and properly bulkheading and abandoning the outfall pipe per state standards/requirements.	4	2024
W40009C01	KK River Jackson Park: Demolition, Salvage & Recycling at 3460 W. Leeds Place - The scope includes demolition, salvage and recycling of a building, earthwork, landfill disposal of soil, and surface restoration at 3460 West Leeds Place in Milwaukee, WI.	1	2025
W10004C01	Milwaukee River Habitat Enhancement - Estabrook Falls - Remove bedrock from the bed of the Milwaukee River to improve hydraulic conditions for passage of native fish. Restore vegetation.	1	2025

MMSD Planned Construction or Services Bids*

October 1, 2024 - September 30, 2025

Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
J06086C01	Building Roof Replacement Phase 4 at Jones Island WRF - The scope includes the replacement of the roofs on two buildings at the Jones Island Water Reclamation Facility.	1	2025
S06048C01	Building Roof Replacement Phase 5 at the South Shore WRF - The scope includes the replacement of the roofs on five buildings at the South Shore Water Reclamation Facility.	1	2025
W20033C01	Menomonee River Levee System Improvements - The scope includes levee and floodwall freeboard improvements along with storm sewer closure improvements integral with or near the Hart Park levee system.	2	2025
J01019C01	Jones Island Force Main Improvements - The scope includes cleaning, televising, spot repairs at five locations, and interior steel surface recoating for the rehabilitation of a 72-inch diameter force main at the Jones Island Water Reclamation Facility.	2	2025
G98026C01	2024 Fresh Coast Highways - The scope includes adding GI features that may include bioswales, native landscaping, and stormwater trees to the project area around the Port Overpass to capture stormwater from the highways and neighboring roads.	2	2025

MMSD Planned Construction or Services Bids*

October 1, 2024 - September 30, 2025

Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
C98044C01	MIS Abandonment in Various Locations - Abandonment and cementecous fill of inactive manholes and pipes throughout the conveyance system.	2	2025
C98063E04	MIS Siphons Preliminary Engineering - Phase 2 - The scope includes condition assessment of siphons to be identified for Phase 2. Siphons will be isolated, cleaned, and then assessed with CCTV and other multi-sensor inspection equipment as specified.	2	2025
C03013C01	Oklahoma Avenue MIS Capacity Improvements - Construction of 3,200 LF of new 48" diameter sewer via microtunneling. Contract also includes relocation of local utilities, abandonment of a pump station and associated site restoration.	3	2025
S01013C02	South Shore Research Facility - Construction of research facility at the SSWRF for the piloting of new wastewater treatment technologies. Contract includes excavation, foundation work, building construction, building electrical, building mechanicals, interior buildout of laboratory and office spaces, and installation of wastewater pilot equipment.	3	2025
M01044C01	HQ and Lab Buildings Remodel - The scope includes remodel of the 1st and 4th floor at MMSD HQ. HVAC improvements and ADA compliant restrooms are also included.	3	2025

MMSD Planned Construction or Services Bids*

October 1, 2024 - September 30, 2025

Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
----------------------------------	--------------------------------	------------------------------	---------------------------

**All schedules are estimates and subject to change. This list will be updated quarterly.*